



PLUMBING SITE PLAN SCALE: 1" = 40'-0"

PLUMBING SYMBOLS	
SYMBOL	DESCRIPTION
	EXISTING SANITARY SEWER MAIN
	EXISTING WATER MAIN
	NEW CITY WATER METER
	SANITARY SEWER LINE
	SANITARY SEWER VENT
	DOMESTIC COLD WATER SPLY. LINE
	DOMESTIC HOT WATER SPLY. LINE
	DOMESTIC HOT WATER RTN. LINE
	VALVE BOX (H.V. AND C.V. SHUT OFF VALVES)
	DOUBLE CHECK ASSEMBLY SET IN BOX
	EXISTING GAS MAIN
	GAS SPLY. LINE (LOW PRESS.)
	GAS SPLY. LINE (HIGH PRESS.)
	GAS METER
	GAS REGULATOR
	GAS STOP (GLOBE VALVE)
	GATE VALVE
	CHECK VALVE
	BALANCING VALVE
	ONE WAY SAN. SWR. CLEAN OUT
	TWO WAY SAN. SWR. CLEAN OUT
	WALL CLEAN OUT
	HOSE BIBB
	FLOOR DRAIN
	TEMP. PRESS. AND RELIEF VALVE
	HOT WATER DISCHARGE LINE
	UNION

PLUMBING SPECIFICATIONS

- GENERAL CONTRACTOR:**
- To provide all cutting, patching, painting, rock removal, concrete work, access doors, (if required)
 - To pay all pro rata charges.
 - To pay any additional costs if a man hole is required by city authorities, in lieu of a sanitary sewer tap.
 - To instruct cabinet manufacturer to install all lavatories and kitchen sinks. (to be furnished by plumber)
 - To pay any costs required to install temporary water meters or temporary gas meters for construction use only.
- HVAC AND AIR CONDITIONING CONTRACTOR:**
- To furnish and install all piping from condensate drain on unit to drain provided by plumber.
 - To make all final connections required for unit.
- PLUMBING CONTRACTOR:**
- To furnish and install a complete plumbing system to conform to city code requirements.
 - To pay all sanitary sewer tap fees and all water meter installation fee required.
 - To pay for gas meter installation, (if required)
 - Materials in General:
 - INSULATION:**
 - Insulate all water piping in exterior walls and in attic spaces.
 - INSULATE - G.R. ONLY WITH 1" THICK WEATHERNE INSUL.
 -
 - SANITARY SEWER:**
 - ALL UNDERGROUND HORIZ. PIPING TO BE CAST IRON.
 - ALL RISERS & VERT. PIPING TO BE PVC PIPE
 -
 - DOMESTIC WATER PIPE:**
 - ALL UNDERGROUND COLD WTR. OUTSIDE BLDGS TO BE PVC PIPE
 - ALL CIRC. HW. & PIPING AROUND TO BE 1" HARD COPR PIPE
 - ALL PIPING UNDER BLDGS TO BE 1" SOFT COPR PIPE
 - GAS PIPE:**
 - UNDERGROUND TO BE POLYETHYLENE PIPE
 - ABV. GROUND TO BE SCHED. 40 STEEL PIPE
 -
 - OTHERS:**
 -
 -
 -
 - WATER HEATERS:**
 -
 -
 -
 - PICTURE TYPE AND ROUGH IN MEASUREMENTS:**

	TYPE	DRAIN	WATER
1. WATER CLOSET		12"	6"
2. BATH, WATER CLOSET		12"	6"
3. LAVATORIES COUNTERTOP		12"	18"
4. LAVATORIES WALL HUNG		12"	18"
5. BATH TUBS		VERIFY	VERIFY
6. KITCHEN SINKS		14"	18"
7. BAR SINKS		18"	18"
8. WASHERS		32"	32"
9. URINALS		VERIFY	VERIFY

NOTES:
 ▲ INSTALL 6x4 REDUCER
 △ INSTALL 6x5 REDUCER

PLUMBING SITE PLAN		JOB NO. 460-P
<p>TEMPO, INC. HVAC AND PLUMBING CONTRACTORS 2252 WISCONSIN ST. DALLAS, TEX. 75229 PHONE 214-241-9475</p>		DATE 7-27-73
		DWN. BY G.M. CKD. BY SCALE NOTED DWG. NO. 1 OF 4