USER: ohl299
PROJECT # 27530 OFFICE: RCH
FILE: 27530 UWTR 03.dgn
TIME: 3:11:40 PM
DATE: 8/11/2010

STA 18+40.71 WATER LINE "A"
INSTALL:
1-12" GATE VALVE
1-12"x8" TEE
22 LF OF 8" PVC
CONNECT TO EX 8" PVC AT
EX WATER VALVE

19+85.180
4" Poly
35' Lt ℄
576.743

STA 21+26.09 WATER LINE "A"
INSTALL:
2-12" GATE VALVE
1-12"x12" TEE
89 LF OF 12" PVC
CONNECT TO PROPOSED 12"
VITRUVIAN WAY WATERLINE

21+99.206
4" Poly
38' Lt ℄
580.513

N

SCALE IN FEET

MATCH LINE STA 18+00

EXIST R.O.W. LINE

UG ELEC

PROP DUCT BANK

12"W

ABANDON EXIST 8" WATERLINE

℄ SPRING VALLEY ROAD

SPRING VALLEY ROAD

EXIST R.O.W. LINE

PROP R.O.W. LINE

8"WTR

UG ELEC

LINE A

12"W

MATCH LINE STA 22+00

12"WTR

VITRUVIAN WAY

12"W

INSTALL 400 LF 12" PVC WATER PIPE

SHEET 37 OF 143

WATERLINE "A"

STA 18+40.71 LINE "A"
INSTALL:
1-12" GATE VALVE
1-12"x8" TEE
22 LF OF 8" PVC
CONNECT TO EX 8"PVC
AT EX WATER VALVE

STA 21+26.09 LINE "A"
INSTALL:
2-12" GATE VALVE
1-12"x12" TEE
89 LF OF 8" PVC
CONNECT TO PROPOSED
12" VITRUVIAN WAY
WATERLINE

595
590
585
580
575
570
565
560

MATCH LINE STA 18+00

PROPOSED GROUND

EXISTING GROUND

PROP 18" RCP
LAT 'B3'
FL=576.81

PROP 12" PVC ON +1.15%

WARNING EX GAS LINE
IN AREA ELEVATION
UNKNOWN

PROP 18" RCP
LAT 'B2'
FL=578.48

MATCH LINE STA 22+00

FL 12"=571.96

FL 12"=575.24

18+00 19+00 20+00 21+00 22+00

HALFF ASSOCIATES, INC.
ENGINEERS · SURVEYORS · SCIENTISTS

PRELIMINARY - FOR INTERIM REVIEW ONLY

These documents are for Interim Review and not intended for Construction, Bidding, or Permit Purposes. They were prepared by, or under the supervision of:

M.E. ROMANOWSKI — 56306 PE# — AUGUST 2010 Date

NO.	REVISION	BY	DATE

TOWN OF ADDISON
DALLAS COUNTY, TEXAS

SPRING VALLEY ROAD

WATER PLAN AND PROFILE STA 18+00 TO 22+00

HALFF
1201 NORTH BOWSER ROAD, RICHARDSON, TEXAS 75081-2275
TEL (214) 346-6280 FAX (214) 739-0095

PROJECT	DESIGN	DRAWN	DATE	FILE	SHEET
27530	XXX	XXX	AUGUST 2010	27530 UWTR 03	WTR-3