


- TRAFFIC CONTROL NOTES**
1. CONTRACTOR IS RESPONSIBLE FOR RIDING ALL TRAFFIC CONTROL SHOWN ON THIS PLAN THAT FALLS OUTSIDE AS WELL AS INSIDE THE LIMIT OF WORK/DISTURBANCE LINE. **NO CHANGE ORDERS WILL BE ACCEPTED OR APPROVED FOR FAILURE TO INCLUDE THESE ITEMS.**
 2. CONTRACTOR SHALL COORDINATE CONSTRUCTION IN SHOPPING CENTER TRAFFIC ZONES WITH THE PROPERTY MANAGER.
 3. CONTRACTOR SHALL PROVIDE A MINIMUM 12 FOOT WIDE TRAVEL LANE DURING STORM DRAIN AND WATER LINE CONSTRUCTION. DRIVE AISLES ARE SUFFICIENTLY WIDE ENOUGH TO ACCOMMODATE STAGED CONSTRUCTION AND A SAFE PATH OF TRAVEL.
 4. FENCING, BARRICADES, TRENCH PLATES AND ALL OTHER NECESSARY SAFETY PRECAUTIONS SHALL BE PROVIDED WHILE EXCAVATIONS ARE OPEN AND HAVE NOT BEEN RETURNED TO EXISTING OR BETTER CONDITION.
 5. CONTRACTOR SHALL REFER TO TPOC STANDARDS FOR TRAFFIC CONTROL SIGNAGE AS APPROPRIATE.
 6. CONTRACTOR SHALL PROVIDE DETOUR INFORMATION AND ALTERNATE ROUTE INFORMATION AT THE MAJOR INTERSECTIONS NEAR THE WORK BEING PERFORMED TO ALLOW MOTORISTS TO CHOOSE AN ALTERNATE PATH OF TRAVEL.

APPROVED FOR CONSTRUCTION
 Tom of Addison
 Infrastructure Operations and Services Department
 APPROVED BY *David Williams*
 DATE *12/17/14*
 16901 Westgrove Dr. Addison, TX 75001 (972)450-2871

All responsibility for the adequacy of these plans remains with the Engineer who prepared them. In approving these plans, the Town of Addison makes no representation of adequacy of the work of the Design Engineer.



<p>SHEET NUMBER: C6.0</p>	<p>PROJECT NAME: LAZY DOG RESTAURANT & BAR</p> <p>PROJECT ADDRESS: VILLAGE ON THE PARKWAY 5100 BELT LINE ROAD, SUITE 500 ADDISON, TX 75254</p> <p>BUILDING DEPT. 2nd SUBMITTAL / BID SET PROJECT #: C-LDR-004</p>		<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>Rev</th> <th>Date</th> <th>Description</th> </tr> </thead> <tbody> <tr> <td>10</td> <td>DEC 14</td> <td>PLAN CHECK COMMENTS</td> </tr> </tbody> </table>	Rev	Date	Description	10	DEC 14	PLAN CHECK COMMENTS		<p>2267 MORNING MESA HENDERSON, NV 89052 702.551.2005 info@valley-cdg.com TBPE Firm No. 14469</p>
Rev	Date	Description									
10	DEC 14	PLAN CHECK COMMENTS									