



- ① Space Bars N and G at every other Bar M. Alternate Bars N and G.
- ② Field cut Bars V 2' from pipe penetrations.
- ③ See sheet 3 of 10, Section A-A for spacing of Bars H.
- ④ Field cut Bars H2 2' from pipe penetrations where applicable.
- ⑤ 14 Eq Spa (Abut 1) (Shown)  
13 Eq Spa (Abut 2)
- ⑥ Space Bars L2 with every Bar wH1 in the stem wall.
- ⑦ 6'-1" Min Splice for Bars A and B. Splice 50% of the Bars on one side of the centerline of structure and the remaining on the other side.
- ⑧ 1'-8" Min Splice for Bars H1 and H2 100% of the bars may be spliced in one location.
- ⑨ Field cut Bars wH1 and wV1 2' from steelarch embeds where applicable.
- ⑩ Bars not shown at centerline of Structure for clarity.
- ⑪ See Sheet 3 of 10, Mask Wall Detail for Bars wL1 spacing.
- ⑫ See Sheet 5 of 10 for Bars wL2 spacing.
- ⑬ See Electrical details.

**STEM WALL ELEVATION**  
SCALE: 3/8" = 1'-0"



THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY ERIC S. CHRISTENSEN, P.E. #85412 ON 05-19-2010. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT. THE RECORD COPY OF THIS DRAWING IS ON FILE AT THE OFFICES OF HALFF ASSOCIATES, 100 NORTH DOWSER ROAD, RICHARDSON, TEXAS, 75081, TYPE FORM #F-312.

Addendum #2		ESC	05/19/10
NO.	REVISION	BY	DATE
<b>TOWN OF ADDISON</b> DALLAS COUNTY, TEXAS			
<b>VITRUVIAN PARK BRIDGES</b> PONTE AVENUE			
<b>ABUTMENT DETAILS -</b> <b>STEM WALL ELEVATION</b>			
		1201 NORTH BOWSER ROAD, RICHARDSON, TEXAS 75081-2275 TEL (214) 346-0200 FAX (214) 790-0096	
PROJECT	DESIGN	DRAWN	DATE
27379	ESC	AHH	APRIL 2010
FILE	SHEET		
-	S1-08		