



ELEVATION  
SCALE: 3/16" = 1'-0"

ESTIMATED QUANTITIES

Item	Unit	Quantity
Two Steel Archs	LB	138,900
Four Embed Anchors	LB	35,240
Eighteen Hangers (2" Dia. Rod w/ #5 Clevis)	LB	4,632
Total	LB	178,772

Notes:  
Slide bearings are subsidiary to embed anchors.  
Hanger quantity includes deck embed.



THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY ERIC S. CHRISTENSEN, P.E. #85412 ON 05-14-2010. ALTERATION OF A SEALED DOCUMENT WITHOUT PROPER NOTIFICATION TO THE RESPONSIBLE ENGINEER IS AN OFFENSE UNDER THE TEXAS ENGINEERING PRACTICE ACT. THE RECORD COPY OF THIS DRAWING IS ON FILE AT THE OFFICES OF HALFF ASSOCIATES, 1201 NORTH BOWSER ROAD, RICHARDSON, TEXAS 75081. TPBE FIRM #E-312.

ADDENDUM #1	REVISION	BY	DATE

TOWN OF ADDISON  
 DALLAS COUNTY, TEXAS  
**VITRUVIAN PARK BRIDGES**  
 PONTE AVENUE  
**ARCH DETAILS - ELEVATION**

1201 NORTH BOWSER ROAD, RICHARDSON, TEXAS 75081-2275  
 TEL (214) 346-6200 FAX (214) 739-0095

PROJECT	DESIGN	DRAWN	DATE	FILE	SHEET
27379	ESC	AHH	APRIL 2010	-	S1-19