



01 SITE PLAN 1" = 30'-0"

EXCEL PARKWAY
NORTH

LOT 2, BLOCK A
EXCEL PLAZA
7.771 ACRE TRACT OF LAND
(338,503 SF.)
PARKING = 122 INSIDE GATE
WILLIAM LOMAX SURVEY ABSTRACT NO. 792
TOWN OF ADDISON
DALLAS COUNTY, TEXAS

- SITE PLAN LEGEND**
- PARKING STRIPE
4" STRIPES ON 2'-0" CENTERS
 - NEW LANDSCAPE
 - EXISTING LANDSCAPE TO REMAIN
 - NEW CONCRETE PAVING
 - FIRE LANE
 - BOUNDARY
 - EXISTING CURB REMAIN
 - NEW CURB
 - NEW SECURITY FENCE WITH ALUMINUM FENCE SLATS.
 - EXISTING LIGHT POLE UNLESS OTHERWISE NOTED
 - EXISTING FIRE HYDRANT
 - FIRE DEPARTMENT CONNECTION

GENERAL NOTES

- A. REFER TO SHEET C1.07 FOR GENERAL NOTES.
- B. REFER TO ELECTRICAL ENGINEER, LANDSCAPE AND TREE MITIGATION SHEETS FOR ADDITIONAL INFORMATION.

SITE PLAN NOTES

- 1 NEW DUMPSTER ENCLOSURE
- 2 NEW SCREEN WALL AROUND NEW GENERATOR
- 3 NEW BOLLARDS. REFER TO DETAIL 05/C1.06.
- 4 NEW LIGHT POLE AND LIGHT FIXTURE HEADS AS INDICATED TO MATCH EXISTING. PROVIDE AND INSTALL CONCRETE LIGHT POLE BASE TO MATCH EXISTING.
- 5 NEW 3'-0" WIDE X FULL HT. PEDESTRIAN GATE WITH CITY APPROVED KNOX BOX. GATE IS TO ALIGN WITH EXISTING FIRE HYDRANT.
- 6 NOT USED
- 7 NEW/RELOCATED CONCRETE WHEEL STOPS. NEW WHEEL STOPS ARE TO MATCH EXISTING. REFER TO DETAIL 07/C1.08.
- 8 NEW LOCATION FOR RELOCATED MAILBOXES. CONTRACTOR TO PROVIDE AND INSTALL NEW CONCRETE PAD/BOLTS TO MATCH EXISTING.
- 9 NEW CONCRETE PAD FOR AIR COMPRESSOR. REFER TO 03/C1.08 AND ENGINEERS DRAWINGS.
- 10 NEW CONCRETE SLAB AND BICYCLE RACK. CREATIVE PIPE, INC. #CPBR2-F-P. COORDINATE EXACT LOCATION WITH THE ARCHITECT. REFER TO 04/C1.08.
- 11 NEW SELECT FILL AND CONCRETE PAVING WHERE EXISTING RAMP IS TO BE REMOVED. REFER TO GEOTECHNICAL REPORT.
- 12 NEW PARKING STRIPES AS INDICATED TO MATCH EXISTING.
- 13 NEW DIRECTIONAL SIGN. REFER TO 11/C1.08.
- 14 NEW DIRECTIONAL SIGN. REFER TO 09/C1.08.
- 15 NEW MONUMENT SIGN. REFER TO DETAIL 02/C1.08
- 16 NEW CONCRETE PAD, FLAG POLE AND FLAG POLE LIGHT.
- 17 NEW WATER HYDRANT. REFER TO 05/C1.08 AND ENGINEERS DRAWINGS.
- 18 NEW ELECTRICAL OUTLET MOUNTED TO COLUMN AT 18" ABOVE GRADE. REFER TO 05/C1.08 AND ENGINEER'S DRAWINGS.
- 19 NEW FIRE LANE STRIPE AS REQUIRED TO MATCH EXISTING.
- 20 NEW PAVEMENT STRIPES TO MATCH EXISTING.
- 21 INSTALL SALVAGED LIGHT POLE AND LIGHT FIXTURE. PROVIDE AND INSTALL NEW BASE TO MATCH EXISTING.
- 22 EXISTING CURB INLET TO BE CONVERTED INTO GRATE INLET.
- 23 INSTALL NEW PIPE AT CONSTANT SLOPE DOWN TO EXISTING SWALE.
- 24 STANDARD HEADWALL.
- 25 RECONSTRUCT EXISTING 18" PIPING TO TIE TO NEW PIPE.
- 26 NEW 18" RCP APPROX. 120 LF.
- 27 EXISTING INLET TO BE REMOVED.
- 28 CONTRACTOR SHALL CONFIRM THAT EXISTING PAVEMENT MEETS REQUIREMENTS FOR CITY FIRE LANE.
- 29 TRENCH FOR DIRECT BURY OF ELECTRICAL CONDUITS FOR NEW LIGHT POLE LOCATIONS.
- 30 (4) NEW BOLLARDS AT GATES. (TYPICAL)

WESTGROVE DRIVE

PROJECT:
UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
16850 WESTGROVE DRIVE SUITES 200 & 300 ADDISON, TEXAS 75001
CITY PROJECT NUMBER PW# 2008-20

ARCHITECT:
S | G | Design
3311 Elm Street, Suite 105
Dallas, Texas 75226
214-742-6044
214-742-6041 Fax

ARCHITECT'S SEAL:

CONSULTANT:

TMBP
CONSULTING ENGINEERS INC.
3303 N. AKARD ST. SUITE 405
DALLAS, TEXAS 75245
TEL: 214-971-2030 FAX: 214-971-2031
THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY JOSEPH T. PITT, P.E. 33844 ON JANUARY 6, 2008

ISSUE HISTORY:

CITY REVIEW	01/07/09

DRAWING INFO:
FILE:
CURRENT ISSUE:
DRAWN BY:
CHECKED BY: JTP
SHEET NUMBER:

SITE PLAN
C1.01