

ESTIMATED QUANTITIES

| ITEM | DESCRIPTION | UNIT | PAVING SHEET | | | SIGNALIZATION SHEET | | | TRAFFIC CONTROL | | | PROJ TOTAL | BID TOTAL |
|------|---|-------|--------------|--|--|---------------------|--|---|-----------------|--|--|------------|-----------|
| | | | 4 | | | 5 | | | 6 | | | | |
| 102 | PREPARING RIGHT-OF-WAY | LS | 1 | | | | | | | | | 1 | |
| 103 | SAW REM & DISP CONC PAVING AND CURB | SQ YD | 42 | | | | | | | | | 42 | |
| 104 | UNCLASSIFIED STREET EXCAVATION | CU YD | 38 | | | | | | | | | 38 | |
| 105 | SODDING FOR EROSION CONTROL | SQ YD | 24 | | | | | | | | | 24 | |
| 106 | 12" 4,000 PSI CONCRETE PAVING CLASS "K" | SQ YD | 118 | | | | | | | | | 118 | |
| 107 | 6" INTEGRAL CURB | LF | 78 | | | | | | | | | 78 | |
| 108 | 8" DR-18 PVC WATER | LF | 8 | | | | | | | | | 8 | |
| 109 | FIRE HYDRANT | EACH | 1 | | | | | | | | | 1 | |
| 110 | REM AND SALVAGE FIRE HYDRANT | EACH | 1 | | | | | | | | | 1 | |
| 111 | 8" X 8" TAP VALVE & SLEEVE | EACH | 1 | | | | | | | | | 1 | |
| 112 | JIGGLE BAR TILES (WHITE) | EACH | | | | 6 | | | | | | 6 | |
| 113 | SYMBOLS (ARROWS) | EACH | | | | 1 | | | | | | 1 | |
| 114 | SYMBOLS (WORD) | EACH | | | | 1 | | | | | | 1 | |
| 115 | PROJECT SIGN | EACH | | | | | | 2 | | | | 2 | |
| 116 | PULL BOX TYPE A | EACH | | | | 1 | | | | | | 1 | |
| 117 | 1 1/4" CONDUIT, TRENCH | LF | | | | 20 | | | | | | 20 | |
| 118 | 3" CONDUIT, TRENCH | LF | | | | 12 | | | | | | 12 | |
| 119 | 3" CONDUIT, BORE | LF | | | | 154 | | | | | | 154 | |
| 120 | CABLE, 20 CONDUCTOR, #12 | LF | | | | 87 | | | | | | 87 | |
| 121 | CABLE, 7 CONDUCTOR, #7 | LF | | | | 158 | | | | | | 158 | |
| 122 | CABLE, #12-XHHW | LF | | | | 20 | | | | | | 20 | |
| 123 | CABLE, #6 BARE | LF | | | | 166 | | | | | | 166 | |
| 124 | 1 PAIR DETECTOR CABLE | LF | | | | 225 | | | | | | 225 | |
| 125 | OPTI-COM CABLE | LF | | | | 140 | | | | | | 140 | |
| 126 | OPTI-COM DETECTOR | EACH | | | | 1 | | | | | | 1 | |
| 127 | FOUNDATION, POLE, TRANSFORMER BASE | EACH | | | | 1 | | | | | | 1 | |
| 128 | POLE, STEEL W/ 40' ARM | EACH | | | | 1 | | | | | | 1 | |
| 129 | SIGNAL HEAD, 3 SECTION | EACH | | | | 2 | | | | | | 2 | |
| 130 | SIGNAL HEAD, 4 SECTION | EACH | | | | 1 | | | | | | 1 | |
| 131 | BACKPLATE, 3 SECTION | EACH | | | | 2 | | | | | | 2 | |
| 132 | BACKPLATE, 4 SECTION | EACH | | | | 1 | | | | | | 1 | |
| 133 | PEDESTRIAN PUSH BUTTON | EACH | | | | 2 | | | | | | 2 | |
| 134 | PEDESTRIAN SIGNAL HEAD | EACH | | | | 2 | | | | | | 2 | |
| 135 | REMOVE AND SALVAGE SIGNAL HEAD | EACH | | | | 3 | | | | | | 3 | |
| 136 | REM. & DISP. POLE FOUNDATION | EACH | | | | 1 | | | | | | 1 | |
| 137 | REMOVE STD. BASE/POLE ASSEM. | EACH | | | | 1 | | | | | | 1 | |
| 138 | REMOVE 16' TO 40' MAST ARM | EACH | | | | 1 | | | | | | 1 | |
| 139 | THERMOPLASTIC 24" STOP BAR | LF | | | | 44 | | | | | | 44 | |
| 140 | ALUMINUM SIGNS | SF | | | | 25 | | | | | | 25 | |
| 141 | SAWCUT - LOOP DETECTOR | LF | | | | 432 | | | | | | 432 | |
| 142 | VEH DETECT CABLE #14 (WHT) | LF | | | | 199 | | | | | | 199 | |
| 143 | VEH DETECT CABLE #14 (BLK) | LF | | | | 233 | | | | | | 233 | |
| 144 | MAINTENANCE OF TRAFFIC | LS | | | | | | 1 | | | | 1 | |

Filename: I:\TRANS\Drawings\T010\Microsta_sheets\sq-quant.dgn



| | | | | | |
|--------------------------|------------------------------|---------|---------|--------|-----------|
| | INTERSECTION IMPROVEMENTS | | | | |
| | SOJOURN DR. AT WESTGROVE DR. | | | | |
| | TOWN OF ADDISON | | | | |
| ESTIMATED QUANTITY SHEET | | | | | |
| DESIGNED | DRAWN | CHECKED | DATE | SCALE | SHEET NO. |
| CAJ | CAJ | CEB | 4/11/00 | N.T.S. | 3 OF 6 |