



(A) FINAL BACKFILL shall consist of approved
material placed in 6" to 8" lifts and compacted
to secure 92% Standard Proctor Density, at
optimum moisture content. Material used shall
exclude boulders, frozen clumps of dirt, rubble,
and any stones or rocks larger than 6" diameter.

(B) INITIAL BACKFILL shall consist of sand
material hauled in from approved source and
shall be placed from the springline of the pipe
to a minimum of 12" above the top of the pipe.
Minimal tamping of backfill directly over top
of pipe is required.

(C) HAUNCHING material shall be sand, similar
to initial backfill above, placed and consolidated
under the pipe haunch, up to the springline
of the pipe, with mechanical tampers
to secure 95% density. (Std. Proctor). Testing shall
be completed prior to backfilling. Density testing
will be paid for by the owner. Paired densities will
be paid for by the contractor.

(D) BEDDING MATERIAL is required to bring trench
bottom to grade, and to provide uniform and adequate
support under the pipe. Finished compacted
depth shall be 6" thickness. Compaction attained
by mechanical tamping, vibration or other methods
should attain 92% Standard Proctor Density.

(E) FOUNDATION materials, if overexcavation occurs
or unstable soils occur in trench bottom, shall
consist of manufactured angular, granular material,
1/2 to 1 1/2" in size, such as crushed stone or rock,
placed by best dumping, minimum compactive effort.

Added Conc. Encasmt. Detail.
Changed 4" SS Lateral to 6". Added B.M. of Gas TEC 12/13-85

Revision By Date

TOWN OF ADDISON
DALLAS COUNTY, TEXAS

WINNWOOD RD. SAN. SEWER IMPROVEMENTS

SEWER PLAN AND PROFILE
STA. 25+00 TO STA. 26+00

GINN, INC.
Consulting Engineers Dallas, Texas

Designed - GF Drawn - ALA Date - OCT., 1985 Job No. - 265

Approved - HWG Checked - JCK Scale - 1" = 20'H/1" = 5'V Sheet 23 of 29