



LOAD CABLES
(SEE NOTE 4)

L	TYPE
1	32' 4E4
3	11' 2E4
4	131' 2E2

EXISTING UTILITY LOCATIONS SHOWN ARE SCHEMATIC IN NATURE AND MAY NOT ACCURATELY REFLECT THE SIZE AND LOCATION OF EACH PARTICULAR UTILITY. SOME UTILITY LINES MAY NOT BE SHOWN. CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ACTUAL FIELD LOCATION AND PROTECTION OF ALL EXISTING UTILITIES WHETHER SHOWN OR NOT. CONTRACTOR SHALL ALSO ASSUME RESPONSIBILITY FOR REPAIRS TO EXISTING UTILITIES, WHETHER SHOWN OR NOT, DAMAGED BY CONTRACTOR'S ACTIVITIES. DIFFERENCES IN HORIZONTAL OR VERTICAL LOCATION OF EXISTING UTILITIES SHALL NOT BE A BASIS FOR ADDITIONAL COMPENSATION. CALL 1-800-344-8371 TWO WORKING DAYS PRIOR TO CONSTRUCTION FOR ONSITE LOCATIONS.

LEGEND

- PROPOSED PULL OR SERVICE BOX (AS NOTED)
- PROPOSED POWER POLE WITH RISER (POWER POLE BY OTHERS)
- PROPOSED TRANSFORMER PAD
- PROPOSED VISTA GEAR PAD
- PROPOSED PME PAD
- PROPOSED ELECTRICAL DUCT BANK MANHOLE
- PROPOSED ELECTRICAL DUCT BANK BY OTHER THAN OPEN CUT
- PROPOSED ELECTRICAL DUCT BANK BY OTHER THAN OPEN CUT B.O.T.O.C.
- PROPOSED ELECTRICAL DUCT BANK BY OPEN CUT
- PROP JOINT TRENCH (FRANCHISE & ONCOR) (SEE NOTE 4)
- PROVIDED METER

NOTE:

- ALL PROFILE ELEVATIONS FOR ELECTRICAL DUCT BANK ARE FOR OUTSIDE BOTTOM OF DUCT BANK UNLESS OTHERWISE SPECIFIED. ALL PROFILE ELEVATIONS FOR ELECTRICAL MANHOLES ARE FOR OUTSIDE BOTTOM OF MANHOLE FLOOR UNLESS OTHERWISE SPECIFIED.
- CONTRACTOR SHALL END AND CAP ALL CONDUIT TERMINATING AT SWITCHGEAR OR TRANSFORMER PADS 12 INCHES ABOVE FINISHED GRADE AND COORDINATE FINAL CONDUIT LOCATIONS WITH ONCOR.
- STEEL ENCASUREMENT PIPE SIZES SHOWN ARE APPROX. AND SHALL BE AS REQUIRED FOR CONSTRUCTION AND RECOMMENDED BY PIPE SPACER MANUFACTURER. PIPE SPACERS SHALL BE DESIGNED AND SUPPLIED BY UNDERGROUND DEVICES, INC. OR APPROVED EQUAL.
- ALL ELECTRICAL LOAD CABLES TO BE INSTALLED IN JOINT TRENCH WITH RELOCATED FRANCHISE UTILITIES EXCEPT AS NECESSARY TO CONNECT TO ELECTRICAL EQUIPMENT OR AS NOTED ON THE PLANS. FOR JOINT TRENCH SEE TELECOM RELOCATION PLAN SHEETS.

HALFF
1201 NORTH BOWSER ROAD, RICHARDSON, TEXAS 75081-2215
TEL: (214) 346-8200 FAX: (214) 798-0985

Signature of Registrant P.E. 3-25-14
Date
FIRM REGISTRATION NUMBER: 312

TOWN OF ADDISON
DALLAS COUNTY, TEXAS

BELT LINE ROAD
UNDERGROUND ELECTRICAL

ONCOR DUCT BANK PLAN AND PROFILE
BELT LINE RD STA 58+00 TO STA 62+00

NO.	REVISION	BY	DATE

PROJECT	DESIGN	DATE	FILE	SHEET
29350	HALFF	HALFF	29350 ELEC 13	ELE-13